



DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:




ROADWAY ELEVATION OF RAIL

(Rail Member showing Elliptical Tube Option, Rectangular Tube Option similar).




INTERMEDIATE WALL JOINT DETAIL

(Showing without raised sidewalk) Provide at all interior bents without slab expansion joints. Space equally in between at 33' Max, 10' Min. Location independent of rail member splices.




ISOMETRIC VIEWS AT END OF BRIDGE

(Rail Member showing Elliptical Tube Option, Rectangular Tube Option similar).




TERMINAL CONNECTION DETAILS



ELEVATION SHOWING TYPICAL REINFORCING PLACEMENT

(Showing without raised sidewalk)



AT BENTS WITH SLAB EXP JOINTS AT BENTS WITHOUT SLAB EXP JOINTS

- 1 Terminal Connectors and associated hardware are to be paid for under the Item "Metal Beam Guard Fence". Attach Metal Beam Guard Fence Transitions to the bridge rail and extend along the embankment unless otherwise shown in the plans.
- 2 Pipe rail sections must have at least two posts but not more than four.
- 3 One shop splice per pipe rail section is permitted with minimum 85 percent penetration. The weld may be square groove or single vee groove. Grind smooth.
- 4 Exp Jt or Splice Jt as required.
- 5 2" Dia Std Pipe (2.375" O.D., 0.154" wall thickness) ASTM-A53 Gr B, A1085 or A500 Gr B. Placed on sidewalk side of rail.
- 6 Unless directed otherwise by the Engineer, the Fabricator may use the rectangular tube in lieu of the elliptical tube for the rail member.
- 7 Increase 2" for structures with overlay.
- 8 Provide bolts of sufficient length to extend 1/2" to 3/4" beyond nut.
- 9 Bolt recesses are only required when pedestrian sidewalks are adjacent to back of rail.
- 10 Place 4 additional Bars R(#5) 3'-8" in length inside Bars U(#5) and centered 2'-0" from end of rail when Terminal Connections are required. Field bend as needed.




COMBINATION RAIL

TYPE C402


FILE: r1std020.dgn	DN: TxDOT	CK: TxDOT	DW: JTR	CK: JMH
©TxDOT July 2014	CONT	SECT	JOB	HIGHWAY
REVISIONS				
03-16: Added Class D, E, or F epoxy to Material Notes.				
DIST	COUNTY	SHEET NO.		

DISCLAIMER: This standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.


DATE: FILE:




ON ABUTMENT WINGWALLS OR CIP RETAINING WALLS



ON CIP RETAINING WALLS (Showing Elliptical Tube Option)




ON BRIDGE SLAB (Showing Elliptical Tube Option)




ON BRIDGE SLAB (Showing Rectangular Tube Option)


SECTIONS THRU RAIL WITHOUT RAISED SIDEWALK ⑥




ON ABUTMENT WINGWALLS OR CIP RETAINING WALLS



ON CIP RETAINING WALLS (Showing Elliptical Tube Option)



ON BRIDGE SLAB (Showing Elliptical Tube Option)



ON BRIDGE SLAB (Showing Rectangular Tube Option)

SECTIONS THRU RAIL WITH RAISED SIDEWALK ⑥

- ⑤ 2" Dia Std Pipe (2.375" O.D., 0.154" wall thickness) ASTM-A53 Gr B, A1085 or A500 Gr B. Placed on sidewalk side of rail.
- ⑥ Unless directed otherwise by the Engineer, the Fabricator may use the rectangular tube in lieu of the elliptical tube for the rail member.
- ⑦ Increase 2" for structures with overlay.
- ⑪ 5 1/2" when vertical reinforcing has closer clear cover over horizontal reinforcing in abutment wingwalls or retaining walls on traffic side of wall.


- ⑫ See "Material Notes" for anchor bolt information.
- ⑬ Top longitudinal slab bar may be adjusted laterally 3" plus or minus to tie reinforcing.
- ⑭ Raised Sidewalk

COMBINATION RAIL


TYPE C402

FILE: r1st0020.dgn	DN: TxDOT	CK: TxDOT	DW: JTR	CK: JMH
©TxDOT July 2014	CONT	SECT	JOB	HIGHWAY
REVISIONS				
03-16: Added Class D, E, or F epoxy to Material Notes.				
DIST	COUNTY			SHEET NO.

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.




RECTANGULAR TUBE SLEEVE MEMBER DETAIL
(See Tube Fabrication Detail)




TUBE FABRICATION DETAILS ⑥

ELLIPTICAL TUBE & ELLIPTICAL SLEEVE MEMBER		
8" x 4 7/8" Ellipse	Elliptical Sleeve Member	
Material	Material	Thickness
6" Dia Std Pipe ASTM-A53 E or S Gr B)	ASTM-A53 Gr B	0.353"
	A36 or A500 Gr B	0.339"
6 3/8" O.D. Pipe x 0.188" API-5LX52	ASTM-A53 Gr B	0.339"
	A36 or A500 Gr B	0.325"
	API-5LX52	0.188"

Notes: Other sections of equal or greater strength are acceptable for elliptical sleeves. The major and minor diameters of the rail member may vary +/- 0.1875" from plan dimension. However, the difference between the outside diameters of the elliptical sleeve and the inside diameters of the rail member must not exceed 0.25 inches.



ELLIPTICAL TUBE WITH RAIL POST & ANCHORAGE DETAILS
(Showing Elliptical Tube Option)



RECTANGULAR TUBE WITH RAIL POST & ANCHORAGE DETAILS ⑥
(Showing Rectangular Tube Option)

- ⑤ 2" Dia Std Pipe (2.375" O.D., 0.154" wall thickness) ASTM-A53 Gr B, A1085 or A500 Gr B. Placed on sidewalk side of rail.
- ⑥ Unless directed otherwise by the Engineer, the fabricator may use the rectangular tube in lieu of the elliptical tube for the rail member.
- ⑬ Sleeve Member 1 1/2" Dia Std Pipe (1.90" O.D., 0.145" wall thickness) ASTM-A53 Gr B or A500 Gr B.

COMBINATION RAIL

TYPE C402

FILE: r1st0020.dgn	DN: TxDOT	CK: TxDOT	DW: JTR	CK: JMH
©TxDOT July 2014	CONT	SECT	JOB	HIGHWAY
REVISIONS				
03-16: Added Class D, E, or F epoxy to Material Notes.	DIST	COUNTY	SHEET NO.	

DATE:
FILE:

DISCLAIMER: The use of this standard is governed by the "Texas Engineering Practice Act". No warranty of any kind is made by TxDOT for any purpose whatsoever. TxDOT assumes no responsibility for the conversion of this standard to other formats or for incorrect results or damages resulting from its use.

DATE: FILE:

RAIL DATA FOR HORIZONTAL CURVES

	RADIUS TO FACE OF RAIL	MAX CHORD LENGTH	CONSTRUCT OR FABRICATE
Rail Members	Over 2800'	29'-0"	Straight rail sections
	Over 1400' thru 2800'	14'-6"	To required radius or to chords shown (18)
	Over 700' thru 1400'	7'-3"	
	Thru 700'	Zero	To required radius (18)

CONSTRUCTION NOTES:

This rail may be slip-formed if approved by the Engineer when epoxy adhesive anchor bolts are used.
 Cap all open ends of tubular steel sections.
 At the contractor's option anchor bolts may be cast with the parapet (See Cast-in-Place Anchor Bolt Options).
 Slip-forming parapet is not allowed if anchor bolts are cast with parapet wall.
 Rail parapet must be plumb unless otherwise approved by the Engineer. Steel posts must be square to the top of parapet. Use epoxy mortar under post base plates if gaps larger than 1/16" exist.
 Pipe rail sections must have at least two posts but not more than four.
 Round or chamfer all exposed edges of steel components 1/16" by grinding prior to galvanizing.
 Chamfer all exposed concrete corners.

MATERIAL NOTES:

Galvanize all steel components except reinforcing steel.
 Anchor bolts must be 3/8" Dia ASTM A193 Grade B7 fully threaded rods with heavy hex nuts, one hardened washer and one (2 1/4" OD) washer each. Embed threaded rods into parapet wall with a Type III, Class C, D, E, or F epoxy anchorage system. Minimum embedment depth is 8". Anchorage system chosen must be able to achieve an ultimate tensile resistance of 34 kips per bolt. The Contractor must provide evidence to the Engineer that this can be achieved. Evidence of adequate tensile resistance can be based on the Manufacturer's published values of ultimate tensile strength (account for anchor spacing and edge distance). Anchor installation, including hole size, drilling, and clean-out, must be in accordance with the Manufacturer's instructions.
 Optional cast-in-place anchor bolts must be 3/8" Dia ASTM A325 or A449 bolts (or A193 Gr B7 or F1554 Gr 105 threaded rods with one tack welded heavy hex nut each) with one heavy hex nut and one hardened steel washer plus one 2 1/4" O.D. steel washer at each bolt. Nuts must conform to A563 requirements.
 Provide Class "C" concrete. Provide Class "C" (HPC) if required elsewhere. Provide Grade 60 reinforcing steel.
 Epoxy coat all rail reinforcement if slab bars are epoxy coated.
 Deformed Welded Wire Reinforcement (WWR) (ASTM A1064) may be substituted for Bars R, and V, as shown. Provide the same laps as required for reinforcing bars.
 Provide bar laps, where required, as follows:

Uncoated ~ #5 = 1'-9"
 Epoxy coated ~ #5 = 2'-7"

GENERAL NOTES:

This rail has been evaluated and accepted to be of equal strength to railings with like geometry, which have been crash tested to meet NCHRP Report 350 TL-3 criteria. This rail can be used for speeds of 50 mph and greater when a TL-3 rated guard fence transition is used. When a TL-2 rated guard fence transition is used, this rail can only be used for speeds of 45 mph and less.




Do not use this railing on bridges with expansion joints providing more than 5" movement.

Rail anchorage details shown on this standard may require modification for select structure types. See appropriate details elsewhere in plans for these modifications.


Submit erection drawings showing panel lengths, rail post spacing, and anchor bolt setting to the Engineer for approval.

Average weight of railing with no overlay: 347 plf total
 313 plf (Conc)
 34 plf (Steel).

Cover dimensions are clear dimensions, unless noted otherwise.
 Reinforcing bar dimensions shown are out-to-out of bar.




- (7) Increase 2" for structures with overlay.
- (12) See "Material Notes" for anchor bolt information.
- (16) For raised sidewalks, add sidewalk height to total bar height. Use sidewalk height at rail's location.
- (17) Slots are not allowed in areas where there is a joint in the concrete parapet between rail post.
- (18) Shop drawings for approval required for tubular steel sections.



OPTIONAL SIDE SLOT DRAIN DETAILS

Note: Center Side Slot Drains between rail posts within the limits shown. Side Slot Drains may be used where shown elsewhere on the plans or as directed by the Engineer. Do not place drains over railroad tracks, lower roadways, or sidewalks. When this rail is used as a separator between a roadway surface and a sidewalk surface, side drain slots will not be permitted.

1/8" Dia Heavy Hex Head Anchor Bolt (ASTM-A325 or A449) or Threaded Rod (ASTM-A193 Gr B7 or F1554 Gr 105) with one Hardened Steel Washer and one 2 1/4" O.D. Steel Washer placed under Heavy Hex Nut. One additional Heavy Hex Nut must be furnished for each Threaded Rod.



CAST-IN-PLACE ANCHOR BOLT OPTIONS (12)

		Bridge Division Standard	
COMBINATION RAIL			
TYPE C402			
FILE: r1std020.dgn	DN: TxDOT	CK: TxDOT	DW: JTR
©TxDOT July 2014	CONT	SECT	JOB
REVISIONS			
03-16: Added Class D, E, or F epoxy to Material Notes.	DIST	COUNTY	SHEET NO.